

業務名		ケース名	ケース No.1	備考		1 / 1
-----	--	------	----------	----	--	-------

検討番号	座標(絶対座標)		擁壁形状				切土高 CH (m)	切土法肩 X座標 X (m)	落石防護柵高 h (m)	判定				数量(m ³ /10.0m)		工事費 (千円/10.0m)		
	X (m)	Y (m)	擁壁高 H1 (m)	前面勾配 1:N1	背面勾配 1:N2	天端幅 B1 (m)				擁壁配置	労働安全	安定計算	落石 防護柵	掘削量	CO量	全体	土工 法面工	擁壁工
1	10.900	12.500	7.000	0.50	0.30	0.900	7.857	12.307	-	OK	OUT	OK	-	165.9	116.6	3,136	563	2,573
2	11.050	13.000	7.500	0.50	0.30	0.800	6.526	11.008	-	OK	OUT	OK	-	159.7	120.6	3,148	455	2,694
3	11.200	13.500	8.000	0.50	0.30	0.700	6.526	11.008	-	OK	OUT	OK	-	159.7	124.1	3,255	448	2,807
4	9.950	11.000	5.500	0.50	0.30	0.700	12.299	20.708	-	OK	OK	OK	-	280.8	74.1	3,995	2,224	1,772
5	9.700	10.500	5.000	0.50	0.30	0.700	12.311	21.073	-	OK	OK	OK	-	311.9	65.6	4,037	2,451	1,586
6	9.450	10.000	4.500	0.50	0.30	0.700	12.324	21.438	-	OK	OK	OK	-	345.5	57.6	4,096	2,689	1,407
7	9.200	9.500	4.000	0.50	0.30	0.700	12.336	21.803	-	OK	OK	OK	-	381.2	50.1	4,120	2,884	1,236
8	10.400	11.500	6.000	0.50	0.30	0.900	12.293	20.552	-	OK	OUT	OK	-	276.4	95.1	4,281	2,144	2,137
9	10.850	12.000	6.500	0.50	0.30	1.100	12.288	20.395	-	OK	OUT	OK	-	274.3	118.6	4,559	2,021	2,539