

業務名		ケース名	No.16	備考		1 / 1
-----	--	------	-------	----	--	-------

検討番号	座標(絶対座標)		擁壁形状				切土高 Ch (m)	切土法肩 X座標 X (m)	落石防 護柵高 h (m)	判 定					数量(m <sup>3</sup> /10.0m)		工事費 (千円/10.0m)		
	X (m)	Y (m)	擁壁高 H1 (m)	前面 1:N1	背面 1:N2	天端幅 B1 (m)				擁壁配置	労働安全	安定計算	落石 防護柵	崩壊土砂 捕捉容量	掘削量	CO量	全体	土工 法面工	擁壁工
1	10.000	6.724	3.000	0.50	0.00	0.500	0.652	10.826	1.55	OK	OK	OUT	OK	OUT	18.9	37.5	1,170	106	938
2	10.000	6.720	3.000	0.50	0.00	0.600	0.656	10.828	1.55	OK	OK	OK	OK	OUT	19.6	40.5	1,212	103	982
3	10.000	7.703	4.000	0.50	0.00	0.500	0.673	10.837	1.55	OK	OK	OUT	OK	OUT	22.2	60.0	1,723	207	1,389
4	10.000	7.699	4.000	0.50	0.00	0.600	0.678	10.839	1.55	OK	OK	OUT	OK	OUT	22.9	64.0	1,779	205	1,447
5	10.000	7.694	4.000	0.50	0.00	0.700	0.682	10.841	1.55	OK	OK	OK	OK	OUT	23.6	68.0	1,835	203	1,505
6	10.000	8.682	5.000	0.50	0.00	0.500	0.695	10.847	1.55	OK	OK	OUT	OK	OK	25.6	87.5	2,364	326	1,911
7	10.000	8.677	5.000	0.50	0.00	0.600	0.699	10.850	1.55	OK	OK	OK	OK	OK	26.3	92.5	2,434	324	1,984